

# Takeoff Tab

Del Taco

Bid No. 104

No.	Name	Height	Area	Quantity1	UOM1	Quantity2	UOM2	Quantity3	UOM3
<b>061</b>									
28	Backing 2x4 Linear Blocking 2x4	0"	(unassigned)	40	LF	15	EA	0	
42	Ply - Shelf * 3/4	0"	(unassigned)	11	SF	0		0	
43	Ply - 1/2" * 1/2	9' 0"	(unassigned)	83	LF	0		0	
57	Ply - 1/2" * 1/2	2' 10"	(unassigned)	24	LF	0		0	
<b>02200 Demolition</b>									
33	Sawcut/Break/Remove Std 4' x 18" sawcut trench - Break and Remove	4"	(unassigned)	133	LF	200	SF	0	
<b>02520 Concrete Paving</b>									
1	Concrete Flatwork	0"	(unassigned)	497	SF	6	CY	0	
<b>02580 Pavement Markings</b>									
3	Handicap Logo	0"	(unassigned)	2	EA	0		0	
4	Striping Pavement Striping/Hashing	0"	(unassigned)	98	LF	0		0	
<b>02843 Bollards</b>									
2	Bollards Bollards	3' 0"	(unassigned)	1	EA	0		0	
<b>03300 Cast In Place Concrete</b>									
49	Curb 6"	6"	(unassigned)	3	LF	0	CY	0	
<b>06400 Millwork/Casework</b>									
69	Upper Cabs	3' 0"	(unassigned)	6	LF	0		0	
70	P-Lam Countertop	0"	(unassigned)	6	LF	0		0	
72	Pencil Drawer	3' 0"	(unassigned)	1	EA	0		0	
73	CPU Cabinet	3' 0"	(unassigned)	1	EA	0		0	
<b>07500 Roofing</b>									
53	Roof Penetrations	0"	(unassigned)	6	EA	0		0	
<b>08100 Doors</b>									
10	Door Count - Interior LH	7' 0"	(unassigned)	1	EA	0		0	
11	Door Count - Interior RH	7' 0"	(unassigned)	3	EA	0		0	
<b>08800 Glazing</b>									
9	Window G	1' 6"	(unassigned)	2	EA	0		0	
25	Window A	1' 6"	(unassigned)	1	EA	0		0	
<b>09250 Drywall</b>									
5	Low Wall Partition 4/A-8 * Wood Framed * 4/A8 * 1/2" Hardi Backer Bd 1 Side * Ceramic Tile * 1/2" Ply 1 side * Almond FRP	2' 10"	(unassigned)	20	LF	58	SF	0	
6	Low Wall Partition NO REFERENCE	2' 4"	(unassigned)	24	LF	56	SF	0	

# Takeoff Tab

Del Taco

Bid No. 104

No.	Name	Height	Area	Quantity1	UOM1	Quantity2	UOM2	Quantity3	UOM3
**Low wall NIC by Others									
	* Wood Framed								
	* 4/A8								
	* 1/2" Hardi Backer Bd 1 Side								
	* Ceramic Tile								
	* 1/2" Ply 1 side								
	* Almond FRP								
8	Partition FH 2x6 @ 10'	0"	(unassigned)	10	LF	0		0	
	* 2/A-10								
	* 12" Hardi 2 sides								
	* 1/2" Gyp to 6" ACH								
	* 2x6 Wood Framing								
12	Cornerbead	10' 0"	(unassigned)	11	EA	0		0	
14	Partition FH 2x4 @ 10'	0"	(unassigned)	11	LF	0		0	
	* 2/A-10								
	* 12" Hardi 2 sides								
	* 1/2" Gyp to 6" ACH								
	* 2x6 Wood Framing								
15	Partition 2x4 NO REFERENCE	0"	(unassigned)	45	LF	0		0	
16	Partition 2x6 NO REFERENCE	0"	(unassigned)	30	LF	0		0	
18	Gyp Bd Soffit Dining 4'	6' 0"	(unassigned)	36	LF	0		0	
	* 3/A8								
	* CB								
	* Drywall at Face to Deck								
20	Gyp Bd Soffit Dining 5'1"	6' 0"	(unassigned)	21	LF	0		0	
22	Gyp Bd Ceiling	0"	(unassigned)	195	SF	3	EA	0	
24	Gyp Bd Soffit LF	8' 0"	(unassigned)	44	LF	0		0	
	* 1/2" Ply								
26	Draft Stop	5' 0"	(unassigned)	35	LF	0		0	
50	Exhaust Shaft	15' 0"	(unassigned)	8	LF	0		0	
51	Gyp Bd Soffit O/ Cooler	3' 0"	(unassigned)	26	LF	0		0	
55	Cement Bd	3' 6"	(unassigned)	24	LF	82	SF	0	
<b>09500 Ceilings</b>									
17	ACT-1 2x2 9'10" AFF	0"	(unassigned)	673	SF	0		0	
21	ACT-1 2x4	0"	(unassigned)	759	SF	0		0	
<b>10150 Compartments</b>									
30	Toilet Partitions	1' 0"	(unassigned)	2	EA	0		0	
<b>10260 Wall and Corner Guard</b>									
27	FRP -9'	9' 0"	(unassigned)	1,202	SF	0		0	
56	FRP -2'10"	2' 10"	(unassigned)	67	SF	0		0	
<b>10500 Lockers</b>									
44	Lockers	6' 0"	(unassigned)	5	EA	0		0	
<b>10520 Fire Ext.</b>									
60	Fire Extinguisher	0"	(unassigned)	3	EA	0		0	
<b>10800 Restroom Accy's</b>									
29	Grab Bar	0"	(unassigned)	2	EA	0		0	

# Takeoff Tab

Del Taco




Bid No. 104

No.	Name	Height	Area	Quantity1	UOM1	Quantity2	UOM2	Quantity3	UOM3
▲ 47	Soap Dispenser	0"	(unassigned)	4	EA	0		0	
● 48	Paper Towel Dispenser	0"	(unassigned)	4	EA	0		0	
■ 61	Toilet Paper Dispenser	0"	(unassigned)	2	EA	0		0	
<b>10820 Mirrors</b>									
■ 62	Restroom Mirror	3"	(unassigned)	3	EA	0		0	
<b>12300 Manufactured casework</b>									
▲ 45	Retractable Bench *****OFCI???????????	0"	(unassigned)	1	EA	0		0	
▲ 46	Key Cabinet *****OFCI???????????	0"	(unassigned)	1	EA	0		0	
▲ 54	Menu Board *****OFCI???????????	0"	(unassigned)	1	EA	0		0	
<b>12320 Manufactured casework</b>									
■ 71	Safe Owner Supplied	0"	(unassigned)	1	EA	0		0	
<b>12400 Furnishings and accessories</b>									
● 23	Stanchion Post Coordinate and Install by GC	0"	(unassigned)	5	EA	0		0	
<b>12540 Restraunt Equipment</b>									
● 58	Stand Up Desk & Cabinet CFCI	0"	(unassigned)	1	EA	0		0	
● 59	Drive Thru Fly Fan CFCI	0"	(unassigned)	1	EA	0		0	
<b>15400 Plumbing</b>									
■ 31	Floor Drain	0"	(unassigned)	6	EA	6	EA	6	EA
■ 32	Floor Sink	0"	(unassigned)	6	EA	6	EA	6	EA
■ 34	Lavatory	0"	(unassigned)	3	EA	0		0	
● 35	Urinal Urinal	0"	(unassigned)	1	EA	0		0	
● 36	Water Closet	0"	(unassigned)	3	EA	0		0	
● 37	Floor Clean Out	0"	(unassigned)	2	EA	0		0	
● 38	Wall Clean Out	0"	(unassigned)	4	EA	4	EA	0	
○ 39	Water Heater	0"	(unassigned)	1	EA	0		0	
■ 40	Hose Bibb	0"	(unassigned)	3	EA	0		0	
■ 41	Gas Line	0"	(unassigned)	85	LF	0		0	
■ 63	Mop Sink	1' 6"	(unassigned)	1	EA	0		0	
▲ 64	Faucet - Mop Sink	0"	(unassigned)	1	EA	0		0	
<b>15500 HVAC</b>									
■ 52	HVAC CURB	0"	(unassigned)	86	SF	0		0	
■ 66	Hood Flue	0"	(unassigned)	1	EA	0		0	
■ 67	Ansul System * OFCI	0"	(unassigned)	1	EA	0		0	
■ 68	Quick Disconnect * OFCI	0"	(unassigned)	1	EA	0		0	
<b>16000 Electrical</b>									

# Takeoff Tab

*Del Taco*

Bid No. 104

No.	Name	Height	Area	Quantity1	UOM1	Quantity2	UOM2	Quantity3	UOM3
 13	Exit Light	1' 0"	(unassigned)	3	EA	0		0	
 19	Ceiling Fan	0"	(unassigned)	2	EA	0		0	
<b>16800 Sound and Video</b>									
 65	Music System	0"	(unassigned)	1	EA	1	EA	1	EA
	* Coordinate and Install by GC								
	* OFCI								